



BERGRIVIER MUNICIPALITY

SUPPLY CHAIN MANAGEMENT

Enquiries: Tyrone April Ref: 8/2/4-2025 Tel: (022) 913 6000 E-mail: april@bergmun.org.za

As per e-mail:

Dear Sir /Madam

NOTICE TO BIDDERS

ADDENDUM: 1

QUOTATION: 8/2/4-2025 (MN30-2025) REFURBISHMENT, REPAIR & REPLACEMENT OF THE FENCING AT THE COMBI-COURT AT THE PELLA PARK SPORTGROUND IN PORTERVILLE

Pursuant to the compulsory site meeting held on Friday, 28 February 2025 at 12H00 find below the issues for clarification as discussed.

1. The due date for the submission of the formal quotations will be changed to Friday, 14 March 2025, 12:00 and all the formal quotations must be submitted in accordance with the provisions set out in the formal quotation document. Kindly note that this document must be signed and submitted with your bid.
2. It is confirmed that proof of Public liability and any other guarantee must only be provided pursuant to appointment, as indicated in the formal quotation specifications.
3. Bidders must note that the entire fence might have to be loosened, removed and the mesh wire must be neatly rolled up, stowed away at the municipal yard and re-used after the new poles were fitted. All **strands** must match existing.
4. It is confirmed that all the corner poles (where fence line was completely damaged) must be replaced.
5. A minimum of 8 stays must be installed at the corners, and same must run in line with the existing fence, 2 braces per corner.
6. The replacement of 50mm (2mm thickness) and 76mm (2mm thickness) poles will be priced per unit (see new pricing schedule). All poles must be hot dipped galvanized to match the existing.
7. Every second pole must be replaced with a 76mm (2mm thickness) poles.
8. Post & Poles
 - o 76 x 4000mm x 2mm corner posts
 - o 50 x 4000mm x 2mm middle posts
 - o 32 x 3000mm x 2mm top and bottom rails
9. At the western section the 3600 x 50 x 2mm thick Diamond mesh must be replaced in full, and a rate per/ m² must be provided. This will allow the municipality to procure any number of square meters if necessary to complete the job.
10. Where needed, the concrete surface must be repaired, especially when new poles are installed, and a rate per m² must be provided in order to make good as follows:
 - o 1 coat Styrene Acrylic bonding mixture including fine sand rubber to be prepared.
 - o 2 coats Aqueous Copolymer Emulsion (Mastic).



BERGRIVIER MUNICIPALITY

11. Colour code for emulsion layer to be sampled by the appointed contractor and repair work to match existing layers.
12. Strands must be supplied where needed, and a rate is provided for it in the revised pricing schedule.
13. Treating of existing surface exhibiting certain defects shall be done as follows:
 - o Colprime E or MC-30 or similar approved (Rate of application shall be 0,7l/m²) (per/l rate)
 - o Slurry Seal: Tack coat using 30% bitumen emulsion (cationic, 0.8 l/m²) (per/l rate)
 - o Slurry applied by hand: < 5mm thick (per/ m³ rate)
 - o Patching of cracks with Styrene Acrylic patch mixture (per/ m³ rate)

Kindly ignore the pricing schedule in the bid document and use this one.

PRICING SCHEDULE

| No. | Description | Rates | Estimated Quantity | Price excl. VAT | VAT@ 15% | Price incl. VAT |
|-----------|--|---------------------|--------------------|-----------------|----------|-----------------|
| 1. | Preliminaries & General | | | | | |
| | 1.1. Water, electricity, site security, insurance, etc. | sum | | | | |
| | 1.2. OHSA (Safety plan, PPE, Medicals, audits, etc.) | sum | | | | |
| 2. | Repair, Replacement & Refurbishment of Fencing | | | | | |
| | Refurbishment of existing Diamond mesh fencing (420m ²) 3600mm x 50mm x 2mm inclusive of straining wires to match existing | per/m ² | 350 | | | |
| | Supply of 76mm x 4000mm x 2mm posts | Per Post | 15 | | | |
| | Supply of 50mm x 4000mm x 2mm middle posts | Per Post | 15 | | | |
| | 32mm x 3000mm x 2mm top and bottom rails | Per Post | 5 | | | |
| | Supply & installation of 8 bracing posts (stays); 4000mm x 50mm | sum | | | | |
| | Allow for 400 x 400 x 600mm of 19/20 MPa concrete for each post. | sum | | | | |
| | Supply & install new 3600mm x 50mm x 2mm thick Diamond mesh. | per/ m ² | 70 | | | |



BERGRIVIER MUNICIPALITY

| | | | | | |
|----|--|--------------------|-----|--|--------------------|
| | inclusive of 2mm straining wires to match existing | | | | |
| | Colprime E or MC-30 or similar approved (0,7l/m ²) | per/L | 1 | | |
| | Slurry Seal: Tack coat using 30% bitumen emulsion (cationic, 0.8 l/m ²) | per/L | 1 | | |
| | Slurry applied by hand: < 5mm thick | per/m ³ | 1 | | |
| | Patching of cracks with Styrene Acrylic patch mixture. | per/m ³ | 1 | | |
| | T Piece 32mm Brackets | Per unit | 5 | | |
| | T Piece 50mm Brackets | Per unit | 5 | | |
| | T Piece 76mm Brackets | Per unit | 5 | | |
| | Take down existing fencing where required, stockpile and transport to Municipal stores. All material taken down will remain municipal property | sum | | | |
| | Install 1m high shade cloth (80% blackout) (Edges to be taped and stitched) with eyelets 1m apart onto fence mesh around fence perimeter. Green in colour. | p/m | 100 | | |
| 3. | Provisional Sum (Including VAT) | | | | R 10 000.00 |
| | Total (VAT Inclusive) | | | | R |

Quantities is used for evaluation purposes and may differ when ordered.

[Signature]
MUNICIPAL MANAGER

DATE: 06.03.2025

Note: Confirmation to the addendum

CONFIRMATION

I (Name and Surname of designated person) hereby declare on behalf of

.....
 (Company's name),



BERGRIVIER MUNICIPALITY

That I take note of the above changes in the bidding documentation and that my offer will incorporate the changes.

Address: Tel no.:
..... Fax no.:
.....

Signature of bidder: Date:

This document must be completed by the bidder (above) and submitted with his offer.